


AD-A072 229


O'BRIEN AND GERE ENGINEERS INC PHILADELPHIA PA JUSTIN--ETC F/G 13/2
NATIONAL DAM INSPECTION PROGRAM. SHOHOLA MARSH DAM (NDI-PA 0041--ETC(U)
FEB 79 DACW31-79-C-0010

NL

UNCLASSIFIED

1 OF 1
AD
A072229





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD A 072229

DDC FILE COPY

DELAWARE RIVER BASIN
SHOHOLA CREEK, PIKE COUNTY
PENNSYLVANIA


LEVEL

SHOHOLA MARSH DAM

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

NDI-PA 00412
PA DER 52-158

DDC
AUG 6 1979
A



PREPARED FOR

DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT, CORPS OF ENGINEERS
BALTIMORE, MARYLAND 21203

FEBRUARY 1979

Distribution Unlimited
Approved for Public Release
Contract No. DACW31-79-C-0010

79 08 06 06 9

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DDC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

12 89p

11 Feb 79

DELAWARE RIVER BASIN

Name of Dam: Shohola Marsh Dam
County & State: Pike County, Pennsylvania
Inventory Number: PA 00412

15 DACW31-79-C-0010

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

6 National Dam Inspection Program.
Shohola Marsh Dam (NDI-PA 00412, PA
DER 52-158), Delaware River Basin,
Shohola Creek, Pike County, Pennsylvania.
Phase I Inspection Report.
Prepared by:

O'BRIEN & GERE ENGINEERS, INC.
JUSTIN & COURTNEY DIVISION

For:

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, MD 21203

Accession For	
NTIS G&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution	
Availability Codes	
Dist.	Avail and/or special
A23	CP

410 760

79 08 06 06 9

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected, and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I REPORT
NATIONAL DAM INSPECTION PROGRAM

Name of Dam: Shohola Marsh Dam
State Located: Pennsylvania
County Located: Pike
Stream: Shohola Creek Coordinates: Latitudes $41^{\circ}23.4'$ Longitude $74^{\circ}58.2'$
Date of Inspection: November 22, 1978

ASSESSMENT

ABSTRACT ↓
Shohola Marsh Dam is a concrete gravity structure which impounds a 1137 acre lake at normal pool elevation. Construction of the dam was completed in July, 1968. Shohola Marsh Reservoir is owned by the Pennsylvania Game Commission and is used as a wildlife habitat.

→ Based on visual observations made during the field inspection, the dam appears to be in good condition. The dam is classified as a "high" hazard structure which indicates there is potential for extensive property damage and possible loss of life in the event of a dam failure.

→ Examination of the results of the hydrologic and hydraulic analyses indicates that the existing spillway system is able to pass approximately 63 percent of the Probable Maximum Flood (PMF) without being overtopped. It appears the spillways are designed for heads less than those associated with the PMF. Negative pressures on the downstream face of the spillway would develop for discharges exceeding approximately 30 percent of the PMF. For discharges in excess of 50 percent of the PMF, cavitation may occur.

→ Stability analyses of the spillway system and the non-overflow portion of the dam reveal that the resultant of forces falls outside the middle third of the base for loadings associated with 1.) Normal and 5 kips per square foot (ksf) ice load, 2.) $\frac{1}{2}$ PMF, 3.) Water to the top of dam, 4.) PMF.

→ Further detailed stability, hydrologic and hydraulic studies should be performed to determine if remedial measures are necessary at this time.

ABSTRACT ↗

A flood warning system should be developed and implemented because of the downstream population areas which are subject to flooding during periods of high precipitation.

O'BRIEN & KANE ENGINEERS, INC.
JUSTIN C. O'BRIEN DIVISION
PROFESSIONAL
WILL M. HEISER
ENGINEER
Will M. Heiser No. 6626E
Vice-President
Pennsylvania Registration # 006926-E

Date: 3/15/79

APPROVED BY G. K. Withers
G. K. WITHERS
Colonel, Corps of Engineers
District Engineer

Date: 11 Apr 79



*OVERVIEW
SHOHOLA FALLS DAM, PIKE COUNTY, PENNSYLVANIA*

TABLE OF CONTENTS

	<u>PAGE</u>
SECTION 1 - PROJECT INFORMATION	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	3
SECTION 2 - ENGINEERING DATA	
2.1 Design	5
2.2 Construction	5
2.3 Operation Data	6
2.4 Evaluation	6
SECTION 3 - VISUAL INSPECTION	
3.1 Findings	7
3.2 Evaluation	7
SECTION 4 - OPERATIONAL FEATURES	
4.1 Procedures	8
4.2 Maintenance of the Dam	8
4.3 Maintenance of Operating Facilities	8
4.4 Warning System in Effect	8
4.5 Evaluation	8
SECTION 5 - HYDRAULICS AND HYDROLOGY	
5.1 Evaluation of Features	9
SECTION 6 - STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	10
SECTION 7 - ASSESSMENT, RECOMMENDATIONS, PROPOSED REMEDIAL MEASURES	
7.1 Dam Assessment	11
7.2 Recommendations, Remedial Measures	11

TABLE OF CONTENTS
(Continued)

PLATES

- APPENDIX A - CHECKLIST, ENGINEERING DATA, DESIGN,
CONSTRUCTION, OPERATION, PHASE I**
- APPENDIX B - CHECKLIST, VISUAL INSPECTION, PHASE I**
- APPENDIX C - HYDROLOGIC & HYDRAULIC DATA**
- APPENDIX D - PHOTOGRAPHS**
- APPENDIX E - DRAWINGS**
- APPENDIX F - SITE GEOLOGY**
- APPENDIX G - STRUCTURAL STABILITY DATA**

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
SHOHOLA MARSH RESERVOIR
NATIONAL ID #PA 00412
DER #52-158

SECTION 1

PROJECT INFORMATION

1.1 General

a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of this inspection is to evaluate the structural and hydraulic conditions of the Shohola Marsh Dam and appurtenant structures, and to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project

a. Dam and Appurtenances. (From information supplied by the Department of Environmental Resources, Commonwealth of Pennsylvania.) Shohola Marsh Reservoir has a concrete gravity dam approximately 800 feet long, with a maximum height of 34 feet. In order to utilize the lake at different surface levels, a combination of spillway openings has been provided.

The base of the dam is seated in rock a minimum depth of 2 feet. Because of fractures prevalent in the rock foundation, a grout curtain is provided along the upstream edge of the base of the dam.

The gravity overflow sections have a maximum height of approximately 25 feet with a base width, at this height, of 23 feet. The overflow sections are formed in an ogee shape. An energy dissipating roller bucket with an 8 foot radius is provided at the toe of the ogee sections. A 25-foot long basin is provided beyond the end of the roller bucket. The end of the basin slopes upward on a 1.5 horizontal to 1 vertical (1.5H:1V) slope in the direction of flow and is covered with a 2-foot blanket of riprap.

The non-overflow sections of the dam have a 3-foot top width. The upstream face batter varies from 1H:5V to 1H:20V. The downstream face slope varies from 1H:1.7V to 1H:4V.

At the right end of the concrete dam an earth fill embankment (maximum height 12 feet) is used to tie into the original ground. This fill has a 20 foot top width and side slopes of 3H:1V. A cut-off trench is extended into the rock foundation and the grout curtain is extended into this region.

The reservoir can be drawn down by means of a 3 foot wide by 4 foot high sluice gate located in the overflow section. The invert of this opening is Elev. 1140.0. The discharge from the sluice gate flows onto the roller bucket at the toe of the overflow section. Stop logs and a trash rack are provided upstream of the sluice gate.

b. Location. Shohola Marsh Reservoir was constructed across Shohola Creek at a point approximately 1000 feet south of the U.S. #6 (Roosevelt Highway) crossing of Shohola Creek in Dingman Township, Pike County, Pennsylvania. The site is approximately 13 miles east of Hawley, Pennsylvania and 10 miles west of Milford, Pennsylvania. The dam site is shown on USGS Quadrangle entitled, "Shohola, PA.-N.Y." at coordinates $N41^{\circ}23.4'$, $W74^{\circ}58.2'$. A regional location plan of Shohola Marsh Reservoir is enclosed as Plate 1, Appendix E.

c. Size Classification. The dam is classified as an "Intermediate" size dam based on its storage capacity of 13,000 Ac. Ft.

d. Hazard Classification. The dam is classified as a "High" hazard structure. This is based on the potential in the event of failure for extensive property damage and possible loss of life. A number of homes are located within the flood plain approximately $1\frac{1}{2}$ miles downstream of the structure.

e. Ownership. The dam is owned by the Pennsylvania Game Commission. All correspondence should be sent to Pennsylvania Game Commission, Mr. Glenn L. Bowers, Executive Director, South Office Building, P.O. Box 1567, Harrisburg, Pennsylvania, 17120

f. Purpose of Dam. The reservoir is used by the Pennsylvania Game Commission as a wild life habitat.

g. Design and Construction History. The application to construct Shohola Marsh Dam was submitted on November 15, 1966, by the Pennsylvania Game Commission. The "Report Upon the Application of the Pennsylvania Game Commission" was prepared on February 8, 1967, by the State of Pennsylvania. The permit to construct Shohola Marsh Dam was issued by the State of Pennsylvania on February 14, 1967.

Construction began on May 17, 1967. Correspondence located in the Department of Environmental Resources (DER) files indicates that it took 8 months to complete the first 20% of construction and only 6 additional months to complete the job. Foundation rock excavation was the item which caused the slow progress during the first 8 months of construction. The dam was officially completed July 31, 1968.

h. Normal Operating Procedures. The reservoir is normally maintained at Elevation 1154.0. By removing stop logs in the service spillway, the reservoir

can be lowered to Elevation 1151.0. By use of the 3 foot wide by 4 foot high sluice gate the impoundment can be lowered to Elevation 1140.0. The hoist for the sluice gate is located on the service bridge. The reservoir is lowered periodically to grow crops for water fowl feeding.

1.3 Pertinent Data

(From information supplied by Pennsylvania DER & USGS)

a.	<u>Drainage Area (sq. miles)</u>	54.0
b.	<u>Discharge at Dam Site (cfs)</u>	
	Max. known flood at dam site	
	Elev. 1158.0	2,770 in 1972 (Agnes)
	Gated Spillway capacity at normal pool	
	Elev. 1154.0	200
	Gated Spillway capacity at maximum pool	
	Elev. 1165.0	277
	Ungated spillway capacity at maximum pool	
	Elev. 1165.0	21,140
c.	<u>Elevation (Feet, USGS Datum)</u>	
	Service spillway with stop logs removed	1151.0
	Service spillway (normal pool)	1154.0
	Lower emergency spillway	1158.0
	Upper emergency spillway	1163.0
	Top of dam	1165.0
	Reservoir drain invert	1140.0
	Service bridge floor	1165.0
	Streambed at centerline of dam	1138.0
	Maximum tailwater	1150.0+
d.	<u>Reservoir (miles)</u>	
	Length of maximum pool	4.1
	Length of normal pool	3.2
	Fetch at normal pool	1.0
e.	<u>Storage (Acre-Feet)</u>	
	Normal pool, Elev. 1154.0	12,610
	Lower emergency spillway, Elev. 1158.0	17,270
	Upper emergency spillway, Elev. 1163.0	23,450
	Top of dam, Elev. 1165.0	26,450
f.	<u>Reservoir Surface (Acres)</u>	
	Normal pool, Elev. 1154.0	1,137
	Lower emergency spillway, Elev. 1158.0	1,230
	Upper emergency spillway, Elev. 1163.0	1,340
	Top of Dam, Elev. 1165.0	1,380

- g. Dam
Type Concrete Gravity
Length 800 Ft.
Height 34 Ft. (maximum)
Top width 3 Ft. non-overflow sections
Side Slope Refer to section 1.2.a
Grout curtain Full length of dam to 40 feet below structure
- h. Diversion and Regulating Tunnel
Does not apply to this site
- i. Spillway
1) Type Concrete truncated ogee weir (with stoplogs)
Length of weir 24.0 Ft.
Crest elevation 1151.0
- 2) Type Concrete ogee weir
Length of weir 68.0 Ft.
Crest elevation 1154.0 Normal Pool
- 3) Type Concrete ogee weir
Length of weir 100.0 Ft.
Crest elevation 1158.0 Lower Emergency Spillway
- 4) Type Concrete square edge weir
Length of weir 125.0 Ft.
Crest elevation 1163.0 Upper Emergency Spillway
- j. Regulating Outlets
Reservoir Drain 3 Ft. horizontal by
4 Ft. vertical sluice gate

SECTION 2

ENGINEERING DATA

2.1 Design

a. Data Available. A summary of engineering data on Shohola Marsh Reservoir is presented on the checklist attached as Appendix A. Principal documents obtained from DER containing pertinent data used for this report are as follows.

1. "Application", "Report Upon the Application", and "Permit" to construct Shohola Marsh Dam, DER, 1966-1967.
2. "Tabulation of Bids" to construct Shohola Marsh Dam issued March 29, 1967.
3. "Construction Progress Reports" prepared by Mr. Frederick Futchko, Project Engineer, Dam Section, Gannett Fleming Corddry and Carpenter, Inc. from, May 31, 1967, through August 7, 1968.
4. "Application for Permit to Draw Dam or Other Body of Water in Accordance with the Act of December 15, 1959" and approval of same for Shohola Marsh Reservoir.
5. Photographs made during construction and at the final inspection.
6. Complete set of construction drawings.

Note: Design data is not available.

b. Design Features. The principal design features for the structure are shown on the drawings enclosed in Appendix E as Plates 1 through 6. A description of the features is discussed in Section 1.2.a.

2.2 Construction

Based on the documentation in the DER files and the construction drawings, supplemented by discussion with the Owner's representative, it is concluded that the dam was constructed as designed. Gannett Fleming Corddry and Carpenter Inc. of Harrisburg, Pennsylvania was the designer and construction manager. Burly Construction Corporation, Hewitt, New Jersey, was the contractor.

2.3 Operation Data

There are no formal operating procedures for the dam. A 24-foot length of the service spillway varies in elevation between Elev. 1151.0 and Elev. 1154.0 with the placing or removing of stop logs. Minimum flow requirements are maintained through the 3-foot horizontal by 4-foot vertical reservoir drain gate which has an invert elevation of 1140.0

2.4 Evaluation

a. Availability. All engineering data reproduced in this report and studied for this investigation were provided by DER and supplemented by conversations with the Owner's representative.

b. Adequacy. The entire design folder is not available for review. Reasonably accurate stability analyses were made using the information provided by DER. The drawings are legible and complete, and the dam appears to be constructed in general conformance with the drawings.

SECTION 3

VISUAL INSPECTION

3.1 Findings

a. General. The observations and comments of the field inspection team are in the checklist which is Appendix B of this report. The appearance of the facility indicates that the dam and its appurtenances were constructed in accordance with the drawings. They are well maintained and in good condition. No underwater areas were inspected.

b. Dam. Some hairline cracking of the concrete was noted. There were no significant indications or evidence observed of distortions in vertical or horizontal alignment or grade that would indicate movement of the dam. The sixth section of the dam from the right abutment bows out slightly in the downstream face from the rest of the dam. This may have been due to the arrangement of formwork during construction.

c. Appurtenant Structures. A railing was broken on the stairs to the service bridge. The Game Commission representative assured us this would be welded. The service bridge platform has a difference in elevation of about $\frac{1}{2}$ inch in adjoining portions of the concrete floor. The floor may have been poured that way during construction.

d. Reservoir. Reconnaissance of the reservoir disclosed no evidence of significant siltation, slope instability, or other features that would significantly affect the storage capacity of the reservoir. The slopes on the perimeter of the reservoir are mild and well vegetated.

e. Downstream Conditions. Approximately 60 yards downstream of the dam the flow drops over Shohola Falls which is about 40 feet high. U.S. route 6 crosses over the creek about 1,000 feet downstream of the dam. The highway bridge offers no restriction to flow because the creek is in a deep gorge and clearance for the bridge is at least 70 feet. From the falls to approximately 1-1/4 miles downstream of the falls, the creek flows through a deep gorge on a slope in excess of 4%. In the event of failure, the next 9 miles would be the potential damage region. The channel gradient is approximately 0.7% in this reach. Slopes are vegetated, generally stable, and in good condition.

3.2 Evaluation

No serious deficiencies were observed during the Phase I Visual Inspection.

SECTION 4

OPERATIONAL PROCEDURES

4.1 Procedures

The Pennsylvania Game Commission has written operating procedures which are covered in Section 1.2.h. Normal operating procedures for this structure do not require a dam tender.

4.2 Maintenance of the Dam

The dam is maintained by the Pennsylvania Game Commission. Normal maintenance is reported to consist of keeping the spillways free of all debris, keeping vegetation cut in the vicinity of the dam, and constantly being alert for possible deterioration of the structure.

4.3 Maintenance of Operating Facilities

The operating facilities are maintained by the Pennsylvania Game Commission. Normal maintenance is reported to consist of annually creosoting the service spillway stop logs and cleaning and lubricating the reservoir drain gate system. The Game Commission has written maintenance procedures.

4.4 Warning System in Effect

There is no formal warning system or procedure established to be followed during periods of exceedingly heavy rainfall. However, it is understood that a representative of the Game Commission is always in the vicinity and available to warn downstream residents of impending high flows.

4.5 Evaluation

The operation and maintenance procedures are satisfactory for the Shohola Marsh Reservoir. A formal warning system should be implemented because of the possibility of loss of life and significant property damage downstream in the event of a failure of the structure.

The representative of the Game Commission told us that the reservoir drain gate is operated on a regular schedule. He would have operated the gate hoist, but he did not have the crank for the hoist with him.

The dam is accessible under all weather conditions for inspection and emergency action.

SECTION 5

HYDRAULICS AND HYDROLOGY

5.1 Evaluation of Features

a. Design Data. The original design information is limited to statements in the Application Report dated February 8, 1967.

Shohola Marsh Reservoir's watershed is about 12 miles long and averages about 5 miles wide, with a total drainage area of 54 square miles. Elevations range from 2000 to 1154 at normal reservoir level. The slope of the watershed adjacent to the reservoir is about 10 percent. The watershed is nearly 100 percent wooded. Portions of the watershed are State Game Lands and State Forests while the balance of the watershed is open to private development. The runoff characteristics of the watershed may undergo change in the future as a result of private development.

The spillway was designed to have a maximum discharge of 21,950 cfs., the "C" curve criterion for this drainage area as specified by DER.

b. Experience Data. Rainfall and water level records are not kept for this dam. The Game Commission representative said that during Tropical Storm Agnes (June, 1972), the water reached elevation 1158.0, the crest of the lower emergency spillway. This corresponds to a discharge of approximately 2,800 cfs (assuming the stoplogs were in place).

c. Visual Observations. On the day of the inspection, there were no indications that the spillways of the dam would be obstructed, or would not operate satisfactorily in the event of a storm.

d. Overtopping Potential. The PMF hydrograph was routed through the reservoir with the starting water surface elevation at the crest of the service spillway (Elev. 1154.0). The inflow and outflow peaks for the PMF are 52,070 cfs and 39,804 cfs respectively. The PMF would overtop the dam by approximately 3 feet. Review of the hydrologic analysis indicates that the spillway system is capable of passing approximately 63 percent of the PMF without overtopping of the non-overflow portions of the dam. Refer to Appendix C for computations.

e. Spillway Adequacy. The spillway system is classified as "inadequate" for discharge of the Spillway Design Flood. The spillway system is not "seriously inadequate" since the spillway can adequately discharge more than 50 percent of the PMF.

SECTION 6

STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations. No structural inadequacies were noted during the visual inspection of the dam. However, some minor surface cracking of the concrete was noted on the non-overflow sections. A complete inspection was not possible due to the overflow conditions.

b. Design & Construction Data. All available material was reviewed. Detailed listing of this data is included in Appendix A and is discussed in Section 2.

The service spillway and the lower emergency spillway are ogee sections. The shape of the crest is such that for heads associated with flows in excess of 30 percent of the PMF, the lower nappe of the overflow can be expected to separate from the spillway face, producing negative pressures on the downstream face of the dam. For discharges in excess of 50 percent of the PMF, cavitation may result. The area of subatmospheric pressure along the downstream face of the structure also adds to the overturning effect of the dam. Analysis of the effect of these negative pressures is beyond the scope of this report and are not included in the calculations, Appendix G.

c. Operating Records. There are no operating records maintained for this structure.

d. Post-Construction changes. There are no reports nor is there any evidence that modifications were made to this dam.

e. Seismic Stability. The dam is located in Seismic Zone 1 of the "Seismic Zone Map of Contiguous States". Normally it can be considered that if a dam in this zone is stable under static loading conditions it can be assumed safe for any expected earthquake conditions. Refer to the following paragraph for stability evaluations of various static loading conditions.

f. Evaluation. Stability analyses of the dam for the entire overflow portion and a typical section of the non-overflow portion show that the stability requirements for overturning are not met: the foundation reaction is not in the middle third of the base for discharges ranging from normal flow with ice load to the PMF event. The computer printouts for the stability analyses are included in Appendix G.

SECTION 7

ASSESSMENT, RECOMMENDATIONS, PROPOSED REMEDIAL MEASURES

7.1 Dam Assessment

a. Evaluation. The visual inspection and review of the material supplied by DER indicates that the structure is in good condition and was built in general conformance with the drawings.

Examination of the hydrologic and hydraulic calculations shown in Appendix C indicate that the spillway system will pass about 63 percent of the PMF. Therefore, the spillway system of the structure is considered to be "Inadequate". As pointed out in paragraph 6.1.b, cavitation may develop during flows exceeding 50 percent of the PMF.

The foundation reaction is not in the middle third of the base for the entire overflow portion and typical section taken in the non-overflow portion of the dam. This is true for discharges ranging from normal flow with ice load to the PMF event.

b. Adequacy of Information. The available information along with visual observations are considered to be sufficient to make a reasonable assessment of the dam. The design folder was not made available for review.

c. Urgency. The recommendations presented in Section 7.2 should be implemented immediately.

d. Necessity for Further Investigation. Further detailed stability and hydrologic and hydraulic studies should be performed to determine if remedial measures are necessary at this time.

7.2 Recommendations, Remedial Measures

a. Facilities.

1) The owner should take necessary action to supplement file records of this dam to include stability analyses indicating the structure's capability to resist sliding, overturning and overstressing when subject to water levels where failure would significantly increase potential for loss of life downstream.

2) Recommendations to strengthen the dam would depend on the results of further detailed stability analyses.

3) Measures should be taken to protect the downstream surface of the overflow sections to prevent damage associated with cavitation.

b. Operation & Maintenance Procedures.

1) In the event of failure there could be extensive property damage and possible loss of life downstream. Therefore, a formal procedure of observation and warning during periods of high precipitation should be developed and implemented. This procedure should include a method of warning downstream residents that high flows are expected along the creek. If abnormally high flows are expected, procedures for evacuating people within the flood plain should be implemented.

2) The dam should be inspected on a yearly basis.

APPENDIX

A

**Check List Engineering Data
Design, Construction, Operation
Phase I**

NAME OF DAM Shohola Marsh Reservoirs
 ID # PA 00412

CHECK LIST
 ENGINEERING DATA
 DESIGN, CONSTRUCTION, OPERATION
 PHASE 1

Sheet 1 of 4

REMARKS

ITEM

AS-BUILT DRAWINGS There are no "As-Built" drawings, but DER files have an 11 sheet full size set of construction drawings.

REGIONAL VICINITY MAP See Plate 1, Appendix E.

CONSTRUCTION HISTORY GFC&C's Project Engineer, Dam Section provided progress reports of the construction and these reports are in DER files.

TYPICAL SECTIONS OF DAM Provided by GFC&C. See Appendix E for drawings.

OUTLETS - PLAN

DETAILS

CONSTRAINTS

DISCHARGE RATINGS

RAINFALL/RESERVOIR RECORDS

See Appendix E for drawings.

None available

None available

ITEM	REMARKS
DESIGN REPORTS	Design drawings were prepared by GFC&C (1966) 11/11 sheets were in DER files.
GEOLOGY REPORTS	None provided in DER files. See Appendix F of this report.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	No data available No data available No data available No data available
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	Complete set of logs of drill holes and test pits are part of the set of drawings.
POST-CONSTRUCTION SURVEYS OF DAM	None
BORROW SOURCES	Concrete gravity overflow dam. Embankment material taken from within work area limits. It is only needed for abutment tie-ins.

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	None
HIGH POOL RECORDS	None. Game Commission representative noted that highest water level has been to the crest of the lower Emergency Spillway (EL.1158.0) during Agnes in 1972.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None
MAINTENANCE OPERATION RECORDS	Records are kept in Pennsylvania Game Commission files.

REMARKS

ITEM

SPILLWAY PLAN

SECTIONS

DETAILS

See Appendix E for details

OPERATING EQUIPMENT
PLANS & DETAILS

See Appendix E for details

MISCELLANEOUS

Material
in DER
files

1. "Application" to construct Shohola Marsh Reservoir issued November 15, 1966.
2. "Report upon the Application of the Pennsylvania Game Commission" by Joseph J. Ellam, Hydraulic Engineer, DER, dated February 8, 1967.
3. "Permit" to construct Shohola Marsh Reservoir issued February 14, 1967.
4. "Tabulation of Bids" to construct Shohola Marsh Reservoir issued March 29, 1967.
5. "Construction Progress Reports" prepared by Mr. Frederick Futchko, Project Engineer, Dam Section, GFC&C, Inc. from May 31, 1967 through August 7, 1968.
6. "Application for Permit to Draw Dam or Other Body of Water in Accordance with the Act of December 15, 1959." and approval of same for Shohola Marsh Reservoir.
7. Photographs made during construction and at the final inspection.

APPENDIX

B

Check List

Visual Inspection

Phase I

Sheet 1 of 11

National

ID # PA 00412

Pool Elevation at Time of Inspection +1154.5 M.S.L. Tailwater at Time of Inspection +1140.0 M.S.L.

George Elias	David Campbell	
Leonard Beck	Robert Bowers	
		Recorder
		Leonard Beck

Mr. Wilmer R. Peoples, Land Manager, Pennsylvania Game Commission accompanied us and answered questions during our inspection.

CONCRETE/MASONRY DAMS

Sheet 2 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
ANY NOTICEABLE SEEPAGE	No leakage observed since flow over the service spillway was occurring at the time of inspection.	Should be inspected when no flow is occurring over the spillways.
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	No problems	None
DRAINS	Could not be seen under water in roller buckets	3" diam. drain holes 10' c.c. in the roller bucket of both the service & lower emergency spillways shown on drawings.
WATER PASSAGES	None	None
FOUNDATION	Sandstone and shale outcrops around dam & in creek channel downstream.	As shown on the drawings the dam is built a minimum of 2 feet into the shale and sandstone foundation.

CONCRETE/MASONRY DAMS

Sheet 3 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Minor cracking in non-overflow sections of the dam on both the left and right side.	The service spillway could not be investigated because of flow over it.
STRUCTURAL CRACKING	None observed	Same as above
VERTICAL AND HORIZONTAL ALIGNMENT	Slight variance in horizontal alignment probably due to forming during construction.	None
MONOLITH JOINTS	No problems	None
CONSTRUCTION JOINTS	No problems	None

EMBANKMENT

Sheet 4 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
SURFACE CRACKS	None observed	None
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed	None
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None observed	None
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	No distortions observed	None
RIPRAP FAILURES	None observed	None

EMBANKMENT

Sheet 5 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
Drains	None	None
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	No discontinuities observed	None
ANY NOTICEABLE SEEPAGE	None observed	None
STAFF GAGE AND RECORDER	None	None

OUTLET WORKS

Sheet 6 of 11

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

CRACKING AND SPALLING OF
CONCRETE SURFACES IN
OUTLET CONDUIT

None observed

None

INTAKE STRUCTURE

Under water at time of
investigation

Trash rack protection
shown on drawings.

OUTLET STRUCTURE

No obstructions to
flow noted

None

OUTLET CHANNEL

No problems observed

None

EMERGENCY GATE

under water at time of
Investigation

3' horizontal by
4' vertical sluice gate
shown on drawings.

UNGATED SPILLWAY

Sheet 7 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
CONCRETE WEIR	There were no obstructions for the service and the emergency spillways.	Refer to section 7.2 for suggested measures to be taken for high flows over both the service and emergency spillway weirs.
APPROACH CHANNEL	There were no obstructions for the service and the emergency spillways.	None
DISCHARGE CHANNEL	There were no obstructions for the service and the emergency spillways	None
BRIDGE AND PIERS	There's about a $\frac{1}{2}$ " difference in the pours of the floor of the service bridge.	This probably happened when the floor was poured.

GATED SPILLWAY

Sheet 8 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
------------------------------	---------------------	-----------------------------------

CONCRETE SILL	N/A	
---------------	-----	--

APPROACH CHANNEL	N/A	
------------------	-----	--

DISCHARGE CHANNEL	N/A	
-------------------	-----	--

BRIDGE AND PIERS	N/A	
------------------	-----	--

GATES AND OPERATION EQUIPMENT	N/A	
----------------------------------	-----	--

INSTRUMENTATION

Sheet 9 of 11

<u>VISUAL EXAMINATION</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
MONUMENTATION/SURVEYS	None	None
OBSERVATION WELLS	None	None
WEIRS	None	None
PIEZOMETERS	None	None
OTHER	None	None

RESERVOIR

Sheet 10 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
------------------------------	---------------------	-----------------------------------

SLOPES

Gentle slopes, heavily
vegetated, no signs of
slides

None

SEDIMENTATION

Insignificant

None

DOWNSTREAM CHANNEL

Sheet 11 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	The channel flows through a steep rocky gorge for the first 1-1/4 miles downstream of the dam. From the gorge to the Delaware River the creek flows through a boulder strewn valley.	None
SLOPES	Through the gorge, the channel slope is better than 4%. Downstream of the gorge the channel gradient is about 0.7%. Where observed the side slopes appear stable.	None
APPROXIMATE NO. OF HOMES AND POPULATION	There are at least 11 homes in the flood plain area downstream of dam (Approx. 50 people)	A formal warning system should be developed & implemented. Procedures for evacuating people within the flood plain should be implemented.

APPENDIX

C

Hydrologic & Hydraulic Data



SUBJECT

Shohda Marsh Dam

SHEET

BY

DATE

JOB NO

TABLE OF CONTENTS APPENDIX C

Hydrologic & Hydraulic Data

PMP Calculations

sk 1

Snyder Coefficients

" 1

Stage vs. Discharge Computations

" 2

HEC I - Dam Safety Version Computer Output

" 3-7

**O'BRIEN & GERE**

SUBJECT

SHOHOLA FALLS DAM

SHEET

1

BY

RRB

DATE

1/12/79

JOB NO.

✓ 1/23/79

HEC 1, DAM SAFETY VERSION PROGRAM CALCULATIONS

DRAINAGE AREA : 54 SQUARE MILES

PMP CALCULATIONS (HMS REPORT 33)

AREA IS IN ZONE 1 OF PMP ALL SEASON ENVELOPE (FIG. 1)

24 HR., 200 SQ. MI. RAINFALL \approx 22"

HR	%	RAINFALL	DRF
6	91	20.0"	20.0"
12	105	23.1"	3.1"
24	115	25.3"	2.2"
48	122	26.8"	1.5"

SNYDER COEFFICIENTSFROM INFO. PROVIDED BY COE (BALT. DISTRICT) ZONE #1

$$C_p = 0.45$$

AND

$$C_t = 1.23$$

$$t_p = C_t (L \cdot L_{ca})^{0.3}$$

$$L \approx 17.5 \text{ miles}$$

$$L_{ca} \approx 5.7 \text{ miles}$$

$$t_p = 1.23 (17.5 \cdot 5.7)^{0.3} = 4.89 \text{ HR.}$$

Checked by
DSC

$L = 17.5$ miles
 $L_{c2} \approx 5.7$ miles

± E'lv. 11650 Spine edged weir 216' long. 246.5' x 3.14 216 = 690.0
± E'lv. 1166.5 Spine edged weir (assumed) 230' long. 246.6' x 3.14 230 = 713.0

[illegible]

Reservoir Drain Discharge (orifice flow)

$Q = \overline{CAV} \sqrt{H}$
 $Q = 0.61 \sqrt{20.0} \times 4.4\%$
 $Q = 5.174 \text{ ft}^3/\text{s}$

$Q = 57.74 \cdot \sqrt{12}$
 $Q = 200 \text{ yds.}$
 $Q = 200 \text{ yds.}$

Q 8 Elev 1165.0
Q - 57.74 $\sqrt{25}$
Q - 277 cfs

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 25 SEP 78

UNV DATED 03/07/79.
 TIME 12.34.14.

SH 4

NATIONAL DAM INSPECTION PROGRAM
 SHOHOLA FALLS DAM
 PMF HYDROGRAPH

JOB SPECIFICATION									
NO	MHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	INSTAN
100	1	0	0	0	0	0	0	-4	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= .20 .30 .40 .50 .60 .70 .80 .90 1.00
 NPLAN= 1 NRTIO= 9 LRTIO= 1

SUB-AREA RUNOFF COMPUTATION

RUNOFF TO RESERVOIR

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
A1	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

INVDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISHOW	ISAME	LOCAL
1	1	54.00	0.00	54.00	0.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	22.00	91.00	105.00	115.00	122.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .852

LOSS DATA

LRUPT	STHCR	DLTKR	RTIOL	ERAIN	STNKS	RTIOK	STRYL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
 TP= 4.89 CP= .45 NTA= 0

RECESSION DATA

STRTO= -1.50 QRCSE= -.05 RTIOR= 2.00

UNIT HYDROGRAPH 44 END-OF-PERIOD ORDINATES, LAG= 4.94 HOURS, CP= .45 VOL= 1.00									
251.	929.	1851.	2699.	3187.	3151.	2797.	2453.	2152.	1888.
1656.	1452.	1274.	1117.	980.	859.	754.	661.	580.	509.
446.	391.	343.	301.	264.	232.	203.	178.	156.	137.
120.	105.	93.	81.	71.	62.	55.	48.	42.	37.
32.	28.	25.	22.						

END-OF-PERIOD FLOW

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
-------	-------	--------	------	------	------	--------	-------	-------	--------	------	------	------	--------

SUM 22.86 20.50 2.36 728391.
 (501.1) (521.1) (60.1) (20625.74)

04 5

HYDROGRAPH ROUTING

ROUTING THROUGH RESERVOIR

ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRY	INAME	ISTAGE	IAUTO
A2	1	0	0	0	0	1	0	0
ROUTING DATA								
QLOSS	CLOSS	AVG	IRES	ISAME	IOPY	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
MSTPS NSTDL								
1	0	0	0.000	0.000	X	TSK	STORA	ISPRAT
			LAG	AMSKK		0.000	12730.	-1
0								
STAGE	1154.00	1154.50	1155.00	1156.00	1158.00	1158.50	1159.00	1160.00
	1163.50	1164.00	1165.00	1166.00	1168.00	1170.00		1161.50
FLOW	0.00	122.00	346.00	981.00	2771.00	3449.00	4273.00	6224.00
	15438.00	17222.00	21142.00	25465.00	35124.00	45974.00		13025.00
CAPACITY=	0.	3090.	7590.	12730.	17300.	23640.	26480.	34180.
ELEVATION=	1139.	1144.	1149.	1154.	1158.	1163.	1165.	1170.
CREL SPWD COOW EXPW ELEV COOL CAREA EXPL								
	1154.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA
TOPEL COOU EXPD DAMWID
1165.0 3.1 1.5 230.

PEAK OUTFLOW IS	4596.	AT TIME	52.00 HOURS
PEAK OUTFLOW IS	8184.	AT TIME	51.00 HOURS
PEAK OUTFLOW IS	11969.	AT TIME	50.00 HOURS
PEAK OUTFLOW IS	15887.	AT TIME	50.00 HOURS
PEAK OUTFLOW IS	20098.	AT TIME	49.00 HOURS
PEAK OUTFLOW IS	24629.	AT TIME	49.00 HOURS
PEAK OUTFLOW IS	29411.	AT TIME	49.00 HOURS
PEAK OUTFLOW IS	34366.	AT TIME	48.00 HOURS
PEAK OUTFLOW IS	39804.	AT TIME	48.00 HOURS

24 6

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS								
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9
				.20	.30	.40	.50	.60	.70	.80	.90	1.00
HYDROGRAPH AT	A1	54.00 (134.86)	1	10414. (264.89)	15621. (442.34)	20829. (589.78)	26035. (737.23)	31242. (884.07)	36449. (1032.12)	41656. (1179.96)	46863. (1327.01)	52070. (1474.45)
	A2	54.00 (139.86)	1	4596. (130.13)	8184. (231.73)	11969. (338.92)	15887. (449.86)	20098. (569.12)	24629. (697.42)	29411. (832.03)	34366. (973.14)	39804. (1127.11)

94 7

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION
STORAGE
OUTFLOW

INITIAL VALUE
1154.00
12730.
0.

SPILLWAY CREST
1154.00
12730.
0.


TOP OF DAM
1165.00
26480.
21162.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.20	1159.17	0.00	18924.	4596.	0.00	52.00	0.00
.30	1160.84	0.00	20923.	8184.	0.00	51.00	0.00
.40	1162.32	0.00	22785.	11969.	0.00	50.00	0.00
.50	1163.63	0.00	24529.	15887.	0.00	50.00	0.00
.60	1164.73	0.00	26102.	20098.	0.00	49.00	0.00
.70	1165.71	.71	27571.	24629.	6.00	49.00	0.00
.80	1166.54	1.54	28846.	29411.	9.00	49.00	0.00
.90	1167.32	2.32	30054.	34366.	11.00	48.00	0.00
1.00	1168.05	3.05	31184.	39804.	12.00	48.00	0.00


APPENDIX

D

Photographs




*SERVICE SPILLWAY WITH STOPLOG
CONTROLLED PORTION TO THE LEFT*




*UPSTREAM VIEW OF SERVICE
SPILLWAY AND OUTLET WORKS*



*SERVICE SPILLWAY AND LOWER EMERGENCY
SPILLWAY LOOKING TOWARDS LEFT ABUTMENT*




UPSTREAM VIEW OF DAM



*ON SERVICE BRIDGE SHOWING
RESERVOIR DRAIN HOIST AND STEM*



*RESERVOIR DRAIN AND STOP LOGGED
PORTION OF SERVICE SPILLWAY*



TYPICAL MINOR SURFACE CRACKING



*FALLS OF SHOHOLA CREEK ABOUT 100 YARDS
DOWNSTREAM OF THE DAM*



GORGE 300 YARDS DOWNSTREAM OF DAM



CHANNEL 3 MILES DOWNSTREAM OF DAM


APPENDIX




E


Drawings

Table of Contents APPENDIX E

<i>Regional Vicinity Map</i>	<i>Plate 1</i>
<i>Location & Reservoir Maps, General Plan and Profile</i>	<i>" 2</i>
<i>Dam Site Foundation Exploration - Logs of Core Borings</i>	<i>" 3</i>
<i>Dam Site Foundation Exploration - Logs of Core Borings & Test Hole</i>	<i>" 4</i>
<i>Foundation Excavation - Grouting Details</i>	<i>" 5</i>
<i>Service & Emergency Spillways, Non-Overflow Sections</i>	<i>" 6</i>
<i>Outlet Works & Wingwalls - Plan, Sections & Details</i>	<i>" 7</i>







RESERVOIR MAP

2000' 1000' 0 1000' 2000' 4000'
SCALE 1" = 2000'


NOTE: RESERVOIR MAP TOPOGRAPHY BASED ON PROVISIONAL MAPS BY U.S. GEOLOGICAL SURVEY

52-158-2


RECEIVED BY: [] FOR: []
RESOURCES: [] DIVISION OF FORESTS & WATERS ON THE DAY OF [] A.D. 18- []
[]
[]

NEED: [] FOR: []
SEE: []
[]

STA 12+57
1570' NON-OVERFLOW SECTION
70' 2 @ 20.0' 4 MONOLITHS @ 25.0' = 100.0'
40.0'



ELEV IN FEET ABOVE M.S.L.



GENERAL NOTES:













1. SECTIONS ARE INDICATED THUS $\frac{1}{2}$ THE UPPER NUMBER INDICATES THE SHEET ON WHICH THE SECTION IS CUT OR SHOWN, AND THE LOWER NUMBER INDICATES THE SECTION NUMBER.
2. PAYMENT ITEM NUMBERS ARE INDICATED THUS (6).
3. FOR SITE TOPOGRAPHY AND PROJECT LAYOUT SEE SHEET 3.
4. ALL AREAS AFFECTED BY CONSTRUCTION WILL BE TOPSOILED AND SEEDED AS DESIGNATED BY THE ENGINEER AND THE BUREAU.

PLATE #2


REVISED			
APPROVALS			
APPROVED BY: [] DIRECTOR OF ENGINEERING AND CONSTRUCTION			
APPROVAL REQUIRED: [] SUPERVISOR ENGINEER/ENGINEER IN CHARGE OF CONSTRUCTION			
APPROVED FOR: []			
SUBMITTED BY: []			
ACCEPTED BY: []			
BY: []			
BUREAU OF ENGINEERING AND CONSTRUCTION			
CHECKED BY: []			
ARCH	STRUC	WATER	ELEC
PROJECT NO. 6.C. 5483-0			
LOCATION AND RESERVOIR MAPS, GENERAL PLAN AND PROFILE			
CONSTRUCTION OF SHONOLA DAM			
STATE GAME LANDS NO 180			
SHONOLA FALLS, PIKE COUNTY, PENNSYLVANIA			
SHEPHERD T. FLEMING, CHIEF ENGINEER, THE BUREAU OF ENGINEERING AND CONSTRUCTION			
DATE: []			
BY: []			
SCALE: []			
SHOWN: []			

ALL DIMENSIONS AND EXISTING CONDITIONS SHALL BE CHECKED AND VERIFIED BY THE CONTRACTOR AT THE SITE

2



LEGEND



- Organic material, topsoil, sod, roots
- Silty CLAY (CL)
- Clayey SILT or clayey SAND and GRAVEL FRAGMENTS (SC)
- Sandy or clayey SILT (ML)
- Silty SAND (SM)

SYMBOLS OVERBURDEN

- SILTY SAND or sandy SILT and GRAVEL FRAGMENTS (GM) or (GM-GV) or (GL-GC)
- Poorly graded SAND (SP) or (SP-SL)
- SAND and GRAVEL (GP-GM)
- GRAVEL or FRAGMENTS with silty SAND (GW) or (GW-GC)
- BOULDERS and COBBLES

GENERAL NOTES

- DRILL HOLES (DH) WERE ACCOMPLISHED BY A 3" I.D. x 2.0' LONG SPOON (UNLESS OTHERWISE SPECIFIED). THESE SAMPLE SPOONS FALLING 10' HOWEVER, IN SOME CASES FACILITATE ADVANCING THE BORING, BUT UNLESS OTHERWISE SPECIFIED.
- THE BORINGS INCLUDED ON THESE DRILLING LOGS ARE THE WORK OF THE IMMEDIATE AREA OF THE WORK, THE PRESENTED IN THE FOUNDATION ENGINEERING.
- LETTER SYMBOLS SUCH AS SC, GC, CL, SP, GP, GM, GW, AND SL, ARE THE SOIL CLASSIFICATION SYSTEM (ASTM).
- THE GROUND WATER LEVEL SHOWN ON THESE LOGS IS THE WATER LEVEL IN THE HOLE AT THE TIME OF DRILLING. IT IS NOT NECESSARILY THE LEVEL AT THE TIME OF THE DRILLING OPERATION.
- DESCRIPTION OF SOILS GIVEN ON THESE LOGS ARE THE WATER CONTENTS IN THE SOIL RECOVERED. THE WATER CONTENTS IN THE SOIL RECOVERED ALL WATER CONTENT MATERIAL UNLESS OTHERWISE NOTED.
- TEST PITS (TP) ARE MACHINE DUG.

ROCK

- SHALE
- SANDSTONE
- SILTSTONE or SANDY SHALE

7. DM-2

[illegible][illegible]

34-108-4

THE UNITED STATES

WATER & POWER

FORESTS & AD

NEW YORK

DATE

DM-2

DM-10

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

[illegible]

24-13

Figure 2.

1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2423	2424	2425	2426	2427	2428	2429	2430	2431	2432	2433	2434	2435	2436	2437	2438	2439	2440	2441	2442	2443	2444	2445	2446	2447	2448	2449	2450	2451	2452	2453	2454	2455	2456	2457	2458	2459	2460	2461	2462	2463	2464	2465	2466	2467	2468	2469	2470	2471	2472	2473	2474	2475	2476	2477	2478	2479	2480	2481	2482	2483	2484	2485	2486	2487	2488	2489	2490	2491	2492	2493	2494	2495	2496	2497	2498	2499	2500	2501	2502	2503	2504	2505	2506	2507	2508	2509	2510	2511	2512	2513	2514	2515	2516	2517	2518	2519	2520	2521	2522	2523	2524	2525	2526	2527	2528	2529	2530	2531	2532	2533	2534	2535	2536	2537	2538	2539	2540	2541	2542	2543	2544	2545	2546	2547	2548	2549	2550	2551	2552	2553	2554	2555	2556	2557	2558	2559	2560	2561	2562	2563	2564	2565	2566	2567	2568	2569	2570	2571	2572	2573	2574	2575	2576	2577	2578	2579	2580	2581	2582	2583	2584	2585	2586	2587	2588	2589	2590	2591	2592	2593	2594	2595	2596	2597	2598	2599	2600	2601	2602	2603	2604	2605	2606	2607	2608	2609	2610	2611	2612	2613	2614	2615	2616	2617	2618	2619	2620	2621	2622	2623	2624	2625	2626	2627	2628	2629	2630	2631	2632	2633	2634	2635	2636	2637	2638	2639	2640	2641	2642	2643	2644	2645	2646	2647	2648	2649	2650	2651	2652	2653	2654	2655	2656	2657	2658	2659	2660	2661	2662	2663	2664	2665	2666	2667	2668	2669	2670	2671	2672	2673	2674	2675	2676	2677	2678	2679	2680	2681	2682	2683	2684	2685	2686	2687	2688	2689	2690	2691	2692	2693	2694	2695	2696	2697	2698	2699	2700	2701	2702	2703	2704	2705	2706	2707	2708	2709	2710	2711	2712	2713	2714	2715	2716	2717	2718	2719	2720	2721	2722	2723	2724	2725	2726	2727	2728	2729	2730	2731	2732	2733	2734	2735	2736	2737	2738	2739	2740	2741	2742	2743	2744	2745	2746	2747	2748	2749	2750	2751	2752	2753	2754	2755	2756	2757	2758	2759	2760	2761	2762	2763	2764	2765	2766	2767	2768	2769	2770	2771	2772	2773	2774	2775	2776	2777	2778	2779	2780	2781	2782	2783	2784	2785	2786	2787	2788	2789	2790	2791	2792	2793	2794	2795	2796	2797	2798	2799	2800	2801	2802	2803	2804	2805	2806	2807	2808	2809	2810	2811	2812	2813	2814	2815	2816	2817	2818	2819	2820	2821	2822	2823	2824	2825	2826	2827	2828	2829	2830	2831	2832	2833	2834	2835	2836	2837	2838	2839	2840	2841	2842	2843	2844	2845	2846	2847	2848	2849	2850	2851	2852	2853	2854	2855	2856	2857	2858	2859	2860	2861	2862	2863	2864	2865	2866	2867	2868	2869	2870	2871	2872	2873	2874	2875	2876	2877	2878	2879	2880	2881	2882	2883	2884	2885	2886	2887	2888	2889	2890	2891	2892	2893	2894	2895	2896	2897	2898	2899	2900	2901	2902	2903	2904	2905	2906	2907	2908	2909	2910	2911	2912	2913	2914	2915	2916	2917	2918	2919	2920	2921	2922	2923	2924	2925	2926	2927	2928	2929	2930	2931	2932	2933	2934	2935	2936	2937	2938	2939	2940	2941	2942	2943	2944	2945	2946	2947	2948	2949	2950	2951	2952	2953	2954	2955	2956	2957	2958	2959	2960	2961	2962	2963	2964	2965	2966	2967	2968	2969	2970	2971	2972	2973	2974	2975	2976	2977	2978	2979	2980	2981	2982	2983	2984	2985	2986	2987	2988	2989	2990	2991	2992	2993	2994	2995	2996	2997	2998	2999	3000	3001	3002	3003	3004	3005	3006	3007	3008	3009	3010	3011	3012	3013	3014	3015	3016	3017	3018	3019	3020	3021	3022	3023	3024	3025	3026	3027	3028	3029	3030	3031	3032	3033	3034	3035	3036	3037	3038	3039	3040	3041	3042	3043	3044	3045	3046	3047	3048	3049	3050	3051	3052	3053	3054	3055	3056	3057	3058	3059	3060	3061	3062	3063	3064	3065	3066	3067	3068	3069	3070	3071	3072	3073	3074	3075	3076	3077	3078	3079	3080	3081	3082	3083	3084	3085	3086	3087	3088	3089	3090	3091	3092	3093	3094	3095	3096	3097	3098	3099	3100	3101	3102	3103	3104	3105	3106	3107	3108	3109	3110	3111	3112	3113	3114	3115	3116	3117	3118	3119	3120	3121	3122	3123	3124	3125	3126	3127	3128	3129	3130	3131	3132	3133	3134	3135	3136	3137	3138	3139	3140	3141	3142	3143	3144	3145	3146	3147	3148	3149	3150	3151	3152	3153	3154	3155	3156	3157	3158	3159	3160	3161	3162	3163	3164	3165	3166	3167	3168	3169	3170	3171	3172	3173	3174	3175	3176	3177	3178	3179	3180	3181	3182	3183	3184	3185	3186	3187	3188	3189	3190	3191	3192	3193	3194	3195	3196	3197	3198	3199	3200	3201	3202	3203	3204	3205	3206	3207	3208	3209	3210	3211	3212	3213	3214	3215	3216	3217	3218	3219	3220	3221	3222	3223	3224	3225	3226	3227	3228	3229	3230	3231	3232	3233	3234	3235	3236	3237	3238	3239	3240	3241	3242	3243	3244	3245	3246	3247	3248	3249	3250	3251	3252	3253	3254	3255	3256	3257	3258	3259	3260	3261	3262	3263	3264	3265	3266	3267	3268	3269	3270	3271	3272	3273	3274	3275	3276	3277	3278	3279	3280	3281	3282	3283	3284	3285	3286	3287	3288	3289	3290	3291	3292	3293	3294	3295	3296	3297	3298	3299	3300	3301	3302	3303	3304	3305	3306	3307	3308	3309	3310	3311	3312	3313	3314	3315	3316	3317	3318	3319	3320	3321	3322	3323	3324
------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------

PLATE #3

[illegible]

IN ACCORDANCE WITH THE ISSUED











THE LOSS REPRESENTS THE LEVEL AT WHICH
PRIOR TO REMOVAL OF THE CASING; IT IS
IN WHICH WATER WAS FIRST ENCOUNTERED IN

LOSS IS BASED ON EXAMINATION OF QUANT SIZE
HAS BEEN NOTED ON THE LOSS WHEN THERE
VARIATION WITH SUBSEQUENT CORING. IT SHOULD
ADVANCES COBBLES, OR EVEN SMALL Boulders
STING AND MAY NOT THEREFORE BE REFLECTED
HIGH RESISTANCE TO DRIVING AS RECORDED
LOSS IS CONSIDERED IN MANY CASES TO BE

C COLUMN OF DRILL HOLE AND TEST PIT
OF DRY WEIGHT) OF THE TOTAL SAMPLE OF
PS ARE DETERMINED ON MINUS 3/4





ALL DIMENSIONS AND EXISTING CONDITIONS TO BE CHECKED AND VERIFIED BY THE CONTRACTOR.

2



GENERAL NOTES:
1. See location map for location of these points.
2. All elevations are in feet above sea level.
3. All soil samples were taken from the surface of the ground.

2




- NOTE**
- USE 1" DIA. BLACK STEEL PIPE FOR 12" DIA. GROUT HOLES
 - USE 2" DIA. BLACK STEEL PIPE FOR 12" DIA. GROUT HOLES
 - IF EXPANSION PLUG IS USED THE TOP OF THE PLUG SHALL BE DRILLED TO 2" DIA. CEMENT PIPE INTO HOLE AFTER DRILLING IS COMPLETE
 - GROUT PIPES THROUGH CONCRETE GROUT CAP AND KEY SHALL BE ACCURATELY PLACED AND FIRMLY SUPPORTED FROM TOE TO HEADING CONCRETE
 - GROUT PIPES STICKING ABOVE THE GROUT KEY ARE WITHIN THE CONCRETE HEADLINE SHALL BE LEFT IN PLACE. ALL OTHER GROUT PIPES SHALL BE CUT FLUSH AFTER GROUTING IS COMPLETE


- GENERAL NOTES**
- CONCRETE GROUT KEY SHALL BE PLACED AT THE 6" OF THE GROUT KEY AND EXTEND 12" ABOVE TOP OF GROUT KEY. SEE DETAIL SHEET 4.
 - CONCRETE GROUT KEY SHALL BE PLACED AT THE 6" OF THE GROUT KEY AND EXTEND 12" ABOVE TOP OF GROUT KEY. SEE DETAIL SHEET 4.
 - CONCRETE GROUT KEY SHALL BE PLACED AT THE 6" OF THE GROUT KEY AND EXTEND 12" ABOVE TOP OF GROUT KEY. SEE DETAIL SHEET 4.
 - CONCRETE GROUT KEY SHALL BE PLACED AT THE 6" OF THE GROUT KEY AND EXTEND 12" ABOVE TOP OF GROUT KEY. SEE DETAIL SHEET 4.
 - CONCRETE GROUT KEY SHALL BE PLACED AT THE 6" OF THE GROUT KEY AND EXTEND 12" ABOVE TOP OF GROUT KEY. SEE DETAIL SHEET 4.

GROUTING DETAILS


NOT TO SCALE




TYPICAL SECTION
STA 11+00-STA 12+00
NON-OVERFLOW SECTION
SCALE 3/16"=1'-0"




TYPICAL SECTION
STA 12+00-STA 12+87
NON-OVERFLOW SECTION
SCALE 3/16"=1'-0"




TYPICAL SECTION
STA 13+87-STA 14+87
SERVICE SPILLWAY
SCALE 3/16"=1'-0"




TYPICAL SECTION
STA 14+87-STA 15+00
NON-OVERFLOW SECTION
SCALE 3/16"=1'-0"



TYPICAL SECTION
STA 15+00-STA 15+80
EMERGENCY SPILLWAY
SCALE 3/16"=1'-0"




TYPICAL SECTION
STA 15+80-STA 16+00
NON-OVERFLOW SECTION
SCALE 3/16"=1'-0"



TYPICAL SECTION
STA 16+00-STA 16+00
NON-OVERFLOW SECTION
SCALE 3/16"=1'-0"

NOTE
ROLLER BUCKET NW EL VARIES FROM
EL 1188.0 @ STA 13+32 TO EL 1187.0 @
STA 13+57.



TYPICAL SECTION
STA. 12+57 - STA. 13+57
EMERGENCY SPILLWAY

BAR SIZE	STEEL			ALUMINUM		
	TENSILE STRENGTH (PSI)			TENSILE STRENGTH (PSI)		
	MINIMUM	LAP	SPICE LENGTH (INCHES)	MINIMUM	LAP	SPICE LENGTH (INCHES)
4	7	12	2	7	6	6
5	8	13	2	8	7	7
6	9	14	2	9	8	8
7	10	15	2	10	9	9
8	11	16	2	11	10	10
9	12	17	2	12	11	11
10	13	18	2	13	12	12
11	14	19	2	14	13	13
12	15	20	2	15	14	14
13	16	21	2	16	15	15
14	17	22	2	17	16	16
15	18	23	2	18	17	17
16	19	24	2	19	18	18
17	20	25	2	20	19	19
18	21	26	2	21	20	20
19	22	27	2	22	21	21
20	23	28	2	23	22	22
21	24	29	2	24	23	23
22	25	30	2	25	24	24
23	26	31	2	26	25	25
24	27	32	2	27	26	26
25	28	33	2	28	27	27
26	29	34	2	29	28	28
27	30	35	2	30	29	29
28	31	36	2	31	30	30
29	32	37	2	32	31	31
30	33	38	2	33	32	32
31	34	39	2	34	33	33
32	35	40	2	35	34	34
33	36	41	2	36	35	35
34	37	42	2	37	36	36
35	38	43	2	38	37	37
36	39	44	2	39	38	38
37	40	45	2	40	39	39
38	41	46	2	41	40	40
39	42	47	2	42	41	41
40	43	48	2	43	42	42
41	44	49	2	44	43	43
42	45	50	2	45	44	44
43	46	51	2	46	45	45
44	47	52	2	47	46	46
45	48	53	2	48	47	47
46	49	54	2	49	48	48
47	50	55	2	50	49	49
48	51	56	2	51	50	50
49	52	57	2	52	51	51
50	53	58	2	53	52	52
51	54	59	2	54	53	53
52	55	60	2	55	54	54
53	56	61	2	56	55	55
54	57	62	2	57	56	56
55	58	63	2	58	57	57
56	59	64	2	59	58	58
57	60	65	2	60	59	59
58	61	66	2	61	60	60
59	62	67	2	62	61	61
60	63	68	2	63	62	62
61	64	69	2	64	63	63
62	65	70	2	65	64	64
63	66	71	2	66	65	65
64	67	72	2	67	66	66
65	68	73	2	68	67	67
66	69	74	2	69	68	68
67	70	75	2	70	69	69








NOTE:
TABLE BASED ON ACI-308-93 (WORKING STRESS DESIGN) WITH
 $f'_c = 3,000$ PSI, $f_y = 60,000$ PSI, AND $f'_s = 60,000$ PSI.





1. ALL REINFORCED CONCRETE SHALL BE CAST IN PLACE IN FULLY DEVELOPED FORMS AND CURING SYSTEMS.
2. ALL REINFORCING STEEL SHALL BE EPOXY COATED WITH AN EPOXY SYSTEM BUILT UP TO MEET REQUIREMENTS FOR REINFORCING CONCRETE (A.C.I. 308-63) SEE TABLE FOR MINIMUM COAT THICKNESS.
3. ALL BAR BENDING: DETAILS SHALL BE IN ACCORDANCE WITH A.C.I. STANDARDS UNLESS OTHERWISE NOTED.
4. REINFORCING STEEL SHALL NOT BE PLACED WITHIN 3" OF CONTRACTION JOINTS.
5. ALL BARS IN PAV CONCRETE WILL BE PAID FOR UNDER ITEM 5.
6. ALL ROLLER BUCKET CONCRETE WILL BE PAID FOR UNDER ITEM 03.
7. ALL WALLS, PIERS AND SLABS WILL BE PAID FOR UNDER ITEM 04.
8. ALL JOINT COF AND KEY CONCRETE WILL BE PAID FOR UNDER ITEM 04.
9. ALL REINFORCING STEEL WILL BE PAID FOR UNDER ITEM 5.

GENERAL NOTES:
FOR OTHER GENERAL NOTES SEE SHEET 2.

PLATE #6

[illegible]





GENERAL NOTICE:
1. FOR GENERAL ORDINATE NOTICES SEE ENTRY 2.
2. FOR OTHER GENERAL NOTICES, SEE ENTRY 1.

PLATE 7

REVISED			
APPROVAL			
NAME OF CONTRACTOR OR ENGINEER ADDRESS CITY AND STATE			
DESIGNED BY		DRAWN BY	
CHECKED BY		APPROVED BY	
BUREAU OF ENGINEERING AND CONSTRUCTION CIVIL DIVISION			
APR	ETG	GLC	GLC
PROJECT NO. G.C.6495-C			
OUTLET TUNNEL AND MAIN DRAINS PLAN SECTION 1 CONSTRUCTION OF TUNNEL & MAIN STATE BANK LANE IN 100 FOOTING AT THE INTERSECTION PROPERTY PLANNING BOARD & LANDMARKS CO. ENGINEERS			
COPIES	REMARKS	REVISIONS	PERIOD
DATE	DESCRIPTION OF REVISION	APPROVED BY (NAME, POSITION)	DATE
DATE	REMARKS	APPROVED BY (NAME, POSITION)	DATE

APPENDIX

F

Site Geology


SITE GEOLOGY

Shohola Marsh Reservoir

Shohola Dam and Reservoir is located in the Eastern Glaciated section of the Appalachian Plateau physiographic province. The site is underlain by varying thicknesses of Pleistocene glacial debris and till which mantle the Devonian age shales and sandstones. The bedrock units, which form part of the Catskill formation, dip gently to the north at about 5° to 8° . In local zones crossbedded sandstones dip to nearly 20° . These units may represent the southeast limb of the minor fold known as the Shohola syncline.

Bedrock units forming the foundation of the concrete gravity dam are fractured and jointed as described in the logs of exploratory holes made during the design stage. These weaknesses in the foundation were treated by pressure grouting which apparently was successful in reducing seepage beneath the structure.

No faulting or other major structural defects are known to exist in this area of the Appalachian Plateau.



APPENDIX

G

Structural Stability Data

SUBJECT

Shohola Marsh Dam

SHEET

BY

DATE

JOB NO

Table of Contents APPENDIX G

<i>Generalized Loading Diagram for Structural Stability Analyses of the Dam</i>	<i>Sheet 1</i>
<i>Stability Analyses of Dam, Sta. 12+00 to Sta. 12+57</i>	<i>" 2-6</i>
<i>Stability Analyses of Dam, Sta. 12+57 to Sta. 13+57</i>	<i>" 7-11</i>
<i>Stability Analyses of Dam, Sta. 13+57 to Sta. 14+57</i>	<i>" 12-16</i>

Generalized Loading Diagram for Structural Stability Analyses of the Dam

FORCES


W_{gd} = Weight of gravity dam

F_{hw} = Force of headwater

F_{emb} = Horizontal Force of Embankment

U = Uplift

F_{tw} = Force of tailwater



Sh 2

 STA. 12+00 TO 12+57 NON-OVERFLOW SECTION SHOHOLA MARSH DAM
 NORMAL FLOOD

PASE ELEVATION= 1135.00FT. TOP ELEVATION= 1165.00FT. BASE WIDTH= 18.50FT. DENSITY= 145.00PCF
 HEADWATER ELEVATION= 1154.00FT. TAILWATER ELEVATION= 1139.50FT. EARTHQUAKE ACCELERATION= 0.0008 (HORIZ), 0.0008 (VERT)
 SILT ELEVATION= 1150.00FT. SILT DENSITY(SUBMERGED)= 69.00PCF SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 50.00PSI SHEAR WIDTH= 18.50FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

PERCENT OF
 HEADWATER
 18.50
 67.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	49.01	11.36	556.96	71.26
HEADWATER	11.26	6.33		
TAILWATER	.63	1.50	.95	106.85
UPLIFT	9.98	10.71		12.74
SILT	2.55	5.00		
D/S SOIL (VERT)	7.00	2.50	17.50	
D/S SOIL (HORIZ)	7.00	5.00	35.00	
			610.40	190.85

 NET HORIZONTAL FORCE= 6.18 KIPS
 NET VERTICAL FORCE= 46.03 KIPS
 NET MOMENT= 419.55KIP-Feet
 X-BAR OF FOUNDATION REACTION= 9.11 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= .14 FEET
 FOUNDATION REACTION PRESSURES*****TOE= 18.04 PSI*****HEEL= 16.52 PSI*****
 OVERTURNING FACTOR OF SAFETY= 3.20
 SLIDING FACTOR OF SAFETY= 5.21
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .13
 SLIDING WITH SHEAR FACTOR OF SAFETY= 26.77(SHEAR ACROSS FULL BASE WIDTH)

SH 3

STA. 12+00 TO 12+57 NON-OVERFLOW SECTION SHOHOLA MARSH DAM

BASE ELEVATION= 1135.00FT. TOP ELEVATION= 1165.00FT. BASE WIDTH= 18.50FT. DENSITY= 145.00PCF
HEADWATER ELEVATION= 1154.00FT. TAILWATER ELEVATION= 1139.50FT. EARTHQUAKE ACCELERATION= .000G (HORIZ).000G (VERT)
SILT ELEVATION= 1150.00FT. SILT DENSITY(SUBMERGED)= 48.00PCF SILT PRESSURE COEFFICIENT(K)= .33
SHEAR STRESS= 50.00PSI SHEAR WIDTH= 18.50FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2
PERCENT OF

HEADWATER
18.50
67.00

LOADING	FORCE(KIPS)	ARM(FEET)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	49.01	11.34	556.96	71.26
HEADWATER	11.24	6.33		
TAILWATER	.63	1.50	.95	106.85
UPLIFT	9.98	10.71		12.74
SILT	2.55	5.00		
D/S SOIL (VERT)	7.00	2.50	17.50	
D/S SOIL (HORIZ)	7.00	5.00	35.00	
ICE LOAD	5.00	27.50		
			*****	137.50
			610.40	328.35

NET HORIZONTAL FORCE= 11.18 KIPS
NET VERTICAL FORCE= 46.03 KIPS
NET MOMENT= 282.05KIP-Feet
X-BAR OF FOUNDATION REACTION= 6.13 FEET
ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 3.12 FEET
*****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM*****
FOUNDATION REACTION PRESSURES*****TOE= 34.78 PSI*****HEEL= -.22 PSI*****
OVERTURNING FACTOR OF SAFETY= 1.86
SLIDING FACTOR OF SAFETY= 2.89
DEVELOPED FRICTION FACTOR (NO SHEAR)= .24
SLIDING WITH SHEAR FACTOR OF SAFETY= 14.80(SHEAR ACROSS FULL BASE WIDTH)

SH 5

STA. 12+00 TO 12+57 NON-OVERFLOW SECTION SHOHOLA MARSH DAM

BASE ELEVATION= 1135.00FT. TOP ELEVATION= 1165.00FT. BASE WIDTH= 18.50FT. DENSITY= 145.00PCF
HEADWATER ELEVATION= 1168.10FT. TAILWATER ELEVATION= 1152.00FT. EARTHQUAKE ACCELERATION= .000G (VERT)
SILT ELEVATION= 1150.00FT. SILT DENSITY(SUBMERGED)= 48.00PCF SILT FRICTION COEFFICIENT(K)= .33
SHEAR STRESS= 50.00PSI SHEAR WIDTH= 18.50FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

PERCENT OF
HEADWATER

.00 51.00
18.50 47.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	49.01	11.36	556.96	
HEADWATER	33.88	10.86		367.85
TAILWATER	9.02	5.66	51.04	
UPLIFT	22.54	9.67		217.96
SILT	2.55	5.00		12.74
			608.00	598.55

NET HORIZONTAL FORCE= 27.41 KIPS

NET VERTICAL FORCE= 26.47 KIPS

NET MOMENT= 9.45KIP-Feet

X-BAR OF FOUNDATION REACTION= .36 FEET

ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 8.89 FEET

*****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****

FOUNDATION REACTION PRESSURES***** 38.59 PSI*****

OVERTURNING FACTOR OF SAFETY= 1.02

SLIDING FACTOR OF SAFETY= .68

DEVELOPED FRICTION FACTOR (NO SHEAR)= 1.04

SLIDING WITH SHEAR FACTOR OF SAFETY= 5.53(SHEAR -ACROSS FULL-BASE WIDTH)

NUMBER OF STATIONS TO DESCRIBE DAM= 4

STATION

ELEVATION

.00 1137.00

14.00 1165.00

17.00 1165.00

18.50 1137.00

STOP 0

3h 6

 STA. 12+00 TO 12+57 NON-OVERFLOW SECTION SHOHOLA MARSH DAM
 172 CH

BASE ELEVATION= 1135.00FT. TOP ELEVATION= 1165.00FT. BASE WIDTH= 18.50FT. DENSITY= 145.00PCF
 HEADWATER ELEVATION= 1162.00FT. TAILWATER ELEVATION= 1149.00FT. EARTHQUAKE ACCELERATION= .0006 (HORIZ) .0006 (VERT)
 SILT ELEVATION= 1150.00FT. SILT DENSITY (SUBMERGED)= 68.00PCF SILT PRESSURE COEFFICIENT (K)= .33
 SHEAR STRESS= 50.00PSI SHEAR WIDTH= 13.50FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

STATION	PERCENT OF HEADWATER
18.50	47.00
18.50	67.00

LOADING	FORCE (KIPS)	ARM (FEET)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	49.01	11.32	556.96	204.50
HEADWATER	22.74	8.99		
TAILWATER	6.12	4.66	28.51	173.75
UPLIFT	17.77	9.72		12.74
SILT	2.55	5.00		
D/S SOIL (VERT)	7.00	2.50	17.50	
D/S SOIL (HORIZ)	7.00	5.00	33.00	
			637.97	391.18

NET HORIZONTAL FORCE= 12.18 KIPS
 NET VERTICAL FORCE= 38.24 KIPS
 NET MOMENT= 246.78 KIP-Feet
 X-BAR OF FOUNDATION REACTION= 6.45 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 2.80 FEET
 FOUNDATION REACTION PRESSURES= 27.33 PSI
 OVERTURNING FACTOR OF SAFETY= 1.63
 SLIDING FACTOR OF SAFETY= 2.20
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .32
 SLIDING WITH SHEAR FACTOR OF SAFETY= 13.14 (SHEAR ACROSS FULL BASE WIDTH)
 NUMBER OF STATIONS TO DESCRIBE DAM= 4

STATION	ELEVATION
18.00	1137.00
18.50	1165.00
18.50	1165.00
18.50	1137.00

Sh 7

 STA. 12+57 TO 13+57 LOWER EMERGENCY SPILLWAY - SHOHOLA MARSH DAM

INTERNAL PULL

BASE ELEVATION= 1133.00FT. TOP ELEVATION= 1158.00FT. BASE WIDTH= 23.00FT. DENSITY= 145.00PCF
 HEADWATER ELEVATION= 1154.00FT. TAILWATER ELEVATION= 1139.50FT. EARTHQUAKE ACCELERATION= 0.000G (HORIZ) 0.000G (VERT)
 SILT ELEVATION= 1145.00FT. SILT DENSITY(SUBMERGED)= 68.00PCF SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 50.00PSI SHEAR WIDTH= 23.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

STATION PERCENT OF HEADWATER
 .00
 23.00 31.00
 67.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	48.83	13.71	669.22	96.22
HEADWATER	13.74	6.99		
TAILWATER	1.32	2.16	2.85	190.63
UPLIFT	14.77	12.91		6.52
SILT	1.63	4.00		293.37
			672.07	

NET HORIZONTAL FORCE= 14.07 KIPS
 NET VERTICAL FORCE= 34.06 KIPS
 NET MOMENT= 378.70KIP-Feet
 X-BAR OF FOUNDATION REACTION= 11.12 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= .38 FEET
 FOUNDATION REACTION PRESSURES= 11.31 PSI
 OVERTURNING FACTOR OF SAFETY= 2.29
 SLIDING FACTOR OF SAFETY= 1.69
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .41
 SLIDING WITH SHEAR FACTOR OF SAFETY= 13.46(SHEAR ACROSS FULL BASE WIDTH)

sh 8

***** STA. 12+57 TO 13+57 LOWER EMERGENCY SPILLWAY - SHOHOLA MARSH DAM *****

***** NUPKAL TULL AND ICE LUN *****

BASE ELEVATION= 1133.00FT. TOP ELEVATION= 1158.00FT. BASE WIDTH= 23.00FT. DENSITY= 145.00PCF
 HEADWATER ELEVATION= 1154.00FT. TAILWATER ELEVATION= 1139.50FT. EARTHQUAKE ACCELERATIONS=.000G (HORIZ),.000G (VERT)
 SILT ELEVATION= 1145.00FT. SILT DENSITY(SUBMERGED)= 68.00PCF SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 50.00PSI SHEAR WIDTH= 23.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

STATION PERCENT OF HEADWATER
 .00 31.00
 23.00 67.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	48.83	13.71	669.22	96.22
HEADWATER	13.76	6.99		
TAILWATER	1.32	2.16	2.85	
UPLIFT	14.77	12.91		190.63
SILT	-1.63	4.00		6.52
ICE LOAD	5.00	20.50		102.50
			*****	*****
			672.07	395.87

NET HORIZONTAL FORCE= 19.07 KIPS
 NET VERTICAL FORCE= 34.06 KIPS
 NET MOMENT= 276.20KIP-Feet
 X-BAR OF FOUNDATION REACTION= 8.11 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 3.39 FEET
 FOUNDATION REACTION PRESSURES*****TOE= 19.38 PSI*****HEEL= 1.19 PSI*****
 OVERTURNING FACTOR OF SAFETY= 1.70
 SLIDING FACTOR OF SAFETY= 1.25
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .56
 SLIDING WITH SHEAR FACTOR OF SAFETY= 9.93(SHEAR ACROSS FULL BASE WIDTH)

Sh 9

SIA. 12+57 TO 13+57 LOWER EMERGENCY SPILLWAY - SHOHOLA MARSH DAM
TOP OF DAM

BASE ELEVATION= 1133.00FT. TOP ELEVATION= 1158.00FT. BASE WIDTH= 23.00FT. DENSITY= 145.00PCF
HEADWATER ELEVATION= 1145.00FT. TAILWATER ELEVATION= 1149.00FT. EARTHQUAKE ACCELERATION= 0.000G (HORIZ) 0.000G (VERT)
SILT ELEVATION= 1145.00FT. SILT DENSITY (SUBMERGED)= 68.00PCF SILT PRESSURE COEFFICIENT(K)= .33
SHEAR STRESS= 50.00PSI SHEAR WIDTH= 23.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

PERCENT OF
HEADWATER
23.00 50.00
.00 67.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	48.83	13.71	669.22	299.00
HEADWATER	30.42	9.83		
TAILWATER	7.99	5.33	42.56	323.93
UPLIFT	26.87	12.06		6.52
SILT	1.63	4.00		
			*****	*****
			711.77	629.45

NET HORIZONTAL FORCE= 24.06 KIPS
NET VERTICAL FORCE= 21.96 KIPS
NET MOMENT= 82.32KIP-Feet
X-BAR OF FOUNDATION REACTION= 3.75 FEET
ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 7.75 FEET
*****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM*****
FOUNDATION REACTION PRESSURES*****TOE= 20.04 PSI*****HEEL= -6.78 PSI*****
OVERTURNING FACTOR OF SAFETY= 1.13
SLIDING FACTOR OF SAFETY= .64
DEVELOPED FRICTION FACTOR (NO SHEAR)= 1.10
SLIDING WITH SHEAR FACTOR OF SAFETY= 7.52(SHEAR ACROSS FULL BASE WIDTH)

 STA. 12+57 TO 13+57 LOWER EMERGENCY SPILLWAY - SHOHOLA MARSH DAM

PERMANENT MAXIMUM FLOOD

BASE ELEVATION= 1133.00FT. TOP ELEVATION= 1158.00FT. BASE WIDTH= 23.00FT. DENSITY= 145.00PCF
MEANWATER ELEVATION= 1168.10FT. TAILWATER ELEVATION= 1152.00FT. EARTHQUAKE ACCELERATION**=.000G (HORIZ),.000G (VERT)
SILT ELEVATION= 1145.00FT. SILT DENSITY(SUBMERGED)= 48.00PCF SILT PRESSURE COEFFICIENT(K)= .33
SHEAR STRESS= 50.00PSI SHEAR WIDTH= 23.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

ATION		PERCENT OF HEADWATER
.00		54.00
23.00		67.00

[illegible]

LOADING	FORCE(KIPS)	ARM(FeET)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	48.83	13.71	669.22	359.45
HEADWATER	35.26	10.20		
TAILWATER	11.26	6.33	71.26	363.04
UPLIFT	30.48	11.91		6.52
SILT	1.63	4.00	*****	*****
			740.48	729.01

NET HORIZONTAL FORCE= 25.62 KIPS
NET VERTICAL FORCE= 18.35 KIPS
NET MOMENT= 11.46 KIP-FEET

X-BAR OF FOUNDATION REACTION = .62 FEET

EXCENTRICITY OF FOUNDATION REACTION FROM CENTER= 10.88 FEET

~~*****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM*****~~

FOUNDATION REACTION PRESSURES *****
OVERTURNING FACTOR OF SAFETY= 1.02

OVERTURNING FACTOR OF SAFETY= .50
SLIDING FACTOR OF SAFETY= .50

DEVELOPED FRICTION FACTOR μ (NO-SHEAR) = 1.40

SLIDING WITH SHEAR FACTOR OF SAFETY = 6.96 (SHEAR ACROSS FULL BASE WIDTH)
 INSTANTIONS OF OGEE PORTION OF SECTION ARE 12.75 AND 19.50

EQUATION OF Ogee CURVATURE IS $Y = .16239 \times X^{**1.85}$

STATION	ELEVATION	NUMBER OF STATIONS TO DESCRIBE DAM= 5
1	100	1
2	100	2
3	100	3
4	100	4
5	100	5

STATION	ELEVATION
1+00	1133.00

12.75	1152.32
1.133,00	

19.50	1158.00
20.50	1158.00

20.50	1157.56
23.00	1135.00

✓ 400000

Sh 12

SIA. 13457 TO 14157 SERVICE SPILLWAY SHOHOLA MARSH DAM
NORMAL POOL

BASE ELEVATION= 1131.00FT. TOP ELEVATION= 1154.00FT. BASE WIDTH= 24.00FT. DENSITY= 145.00PCF
HEADWATER ELEVATION= 1154.00FT. TAILWATER ELEVATION= 1139.50FT. EARTHQUAKE ACCELERATION= .000G (VERT)
SILT ELEVATION= .00FT. SILT DENSITY (SUBMERGED)= .00PCF. SILT PRESSURE COEFFICIENT(K)= .33
SHEAR STRESS= 50.00PSI SHEAR WIDTH= 24.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

STATION PERCENT OF
HEADWATER
.00 37.00
24.00 67.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	52.58	13.88	729.90	126.41
HEADWATER	16.50	7.66		
TAILWATER	2.25	2.83	6.38	235.60
UPLIFT	17.91	13.15	***** 736.28	***** 362.01

NET HORIZONTAL FORCE= 14.25 KIPS
NET VERTICAL FORCE= 34.66 KIPS
NET MOMENT= 374.27KIP-Feet
X-BAR OF FOUNDATION REACTION= 10.80 FEET
ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 1.20 FEET
FOUNDATION REACTION PRESSURES*****TOE= 13.05 PSI*****HEEL= 7.01 PSI*****
OVERTURNING FACTOR OF SAFETY= 2.03
SLIDING FACTOR OF SAFETY= 1.70
DEVELOPED FRICTION FACTOR (NO SHEAR)= .41
SLIDING WITH SHEAR FACTOR OF SAFETY= 13.83(SHEAR ACROSS FULL BASE WIDTH)

Sh 13

 STA. 13457 TO 14457 SERVICE SPILLWAY SHOMOLA MARSH DAM
 MURRAY FLOOD GATE ICE LOAD

BASE ELEVATION= 1131.00FT. TOP ELEVATION= 1154.00FT. BASE WIDTH= 24.00FT. DENSITY= 145.00PCF
 HEADWATER ELEVATION= 1154.00FT. TAILWATER ELEVATION= 1139.50FT. EARTHQUAKE ACCELERATION= 0.0006 (HORIZ) 0.0006 (VERT)
 SILT ELEVATION= 0.00FT. SILT DENSITY (SUBMERGED)= 0.00PCF. SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 50.00PSI SHEAR WIDTH= 24.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

STATION PERCENT OF HEADWATER
 .00 37.00
 24.00 67.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	52.58	13.88	729.90	126.41
HEADWATER	16.50	7.66		
TAILWATER	2.25	2.83	6.38	
UPLIFT	17.91	13.15		235.60
ICE LOAD	5.00	22.50		112.50
			*****	*****
			736.28	474.51

 NET HORIZONTAL FORCE= 19.25 KIPS
 NET VERTICAL FORCE= 34.66 KIPS
 NET MOMENT= 261.77KIP-Feet
 X-BAR OF FOUNDATION REACTION= 7.55 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 4.45 FEET
 *****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM*****
 FOUNDATION REACTION PRESSURES*****HEEL= 21.14 PSI*****TOE= -1.13 PSI*****
 OVERTURNING FACTOR OF SAFETY= 1.55
 SLIDING FACTOR OF SAFETY= 1.26
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .56
 SLIDING WITH SHEAR FACTOR OF SAFETY= 10.24(SHEAR ACROSS FULL BASE WIDTH)

Sh 14

SIA. 13452 TO 1457 SEWICE SPILLWAY SHOHOLA MARSH DAM
TOP OF DAM

BASE ELEVATION= 1131.00FT. TOP ELEVATION= 1154.00FT. BASE WIDTH= 24.00FT. DENSITY= 145.00PCF
HEADWATER ELEVATION= 1165.00FT. TAILWATER ELEVATION= 1149.00FT. EARTHQUAKE ACCELERATION= 0.000G (HORIZ). 0.000G (VERT)
SILT ELEVATION= .00FT. SILT DENSITY(SUBMERGED)= .00PCF. SILT PRESSURE COEFFICIENT(N)= .33
SHEAR STRESS= 50.00PSI. SHEAR WIDTH= 24.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

STATION PERCENT OF HEADWATER
.00 53.00
24.00 67.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	52.58	13.88	729.90	
HEADWATER	32.29	9.54		308.09
TAILWATER	10.11	5.99	60.59	
UPLIFT	30.55	12.47		380.87
			790.49	688.96

NET HORIZONTAL FORCE= 22.18 KIPS
NET VERTICAL FORCE= 22.03 KIPS
NET MOMENT= 101.53 KIP-Feet
X-BAR OF FOUNDATION REACTION= 4.61 FEET
ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 7.39 FEET
*****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM***
FOUNDATION REACTION PRESSURES*****TOE= 18.15 PSI*****HEEL= -5.40 PSI*****
OVERTURNING FACTOR OF SAFETY= 1.15
SLIDING FACTOR OF SAFETY= .70
DEVELOPED FRICTION FACTOR (NO SHEAR)= 1.01
SLIDING WITH SHEAR FACTOR OF SAFETY= 8.48(SHEAR ACROSS FULL BASE WIDTH)

SH 15

 STA. 13+57 TO 14+57 SERVICE SPILLWAY SHOHOLA MARSH DAM
 KONGALE MAXIMUM FLOOD

BASE ELEVATION= 1131.00FT. TOP ELEVATION= 1154.00FT. BASE WIDTH= 24.00FT. DENSITY= 145.00PCF
 HEADWATER ELEVATION= 1148.10FT. TAILWATER ELEVATION= 1152.00FT. EARTHQUAKE ACCELERATION= .0006 (HORIZ), .0006 (VERT)
 SILT ELEVATION= .00FT. SILT DENSITY(SUMMERGED)= .00PCF SILT PRESSURE COEFFICIENT(K)= .33
 SHEAR STRESS= 50.00PSI SHEAR WIDTH= 24.00FT. FRICTION FACTOR= .70

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

PERCENT OF
 HEADWATER

.00
 24.00
 57.00

LOADING	FORCE(KIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	52.58	13.88	729.90	359.26
HEADWATER	36.74	9.78		
TAILWATER	13.76	6.99	96.22	424.49
UPLIFT	34.45	12.32	*****	*****
			826.12	783.74

NET HORIZONTAL FORCE= 22.98 KIPS
 NET VERTICAL FORCE= 18.13 KIPS
 NET MOMENT= 42.37KIP-Feet
 X-BAR OF FOUNDATION REACTION= 2.34 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 9.66 FEET
 *****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****TENSION AT HEEL OF DAM***
 FOUNDATION REACTION PRESSURES*****TUE= 17.92 PSI*****HEEL= -7.43 PSI*****
 OVERTURNING FACTOR OF SAFETY= 1.05
 SLIDING FACTOR OF SAFETY= .55
 DEVELOPED FRICTION FACTOR (NO SHEAR)= 1.27
 SLIDING WITH SHEAR FACTOR OF SAFETY= 8.07(SHEAR ACROSS FULL BASE WIDTH)
 STATIONS OF OGEE PORTION OF SECTION ARE 8.00 AND 20.28
 EQUATION OF OGEE CURVATURE IS Y= .09864X+1.85
 NUMBER OF STATIONS TO DESCRIBE DAM= 5

STATION ELEVATION
 .00 1131.00
 8.00 1143.49
 20.28 1154.00
 22.13 1153.15
 24.30 1138.00

STOP 0

94 16

 STA. 13+57 TO 14+72 SERVICE SPILLWAY BIRCHMOUNT DAM
 172 FT

BASE ELEVATION= 1131.00FT. TOP ELEVATION= 1154.00FT. BASE WIDTH= 24.00FT. DENSITY= 143.00PCF
 HEADWATER ELEVATION= 1163.65FT. TAILWATER ELEVATION= 1149.00FT. EARTHQUAKE ACCELERATION= 0.000G (HORIZ), 0.000G (VERT)
 SILT ELEVATION= 1163.65FT. SILT DENSITY(SUBMERGED)= 0.00PCF SILT PRESSURE COEFFICIENT(K)= 1.33
 SHEAR STRESS= 50.00PSI SHEAR WIDTH= 24.00FT. FRICTION FACTOR= 0.0

NUMBER OF STATIONS TO DESCRIBE UPLIFT= 2

STATION PERCENT OF HEADWATER
 24.00 53.00
 47.00

LOADING	FORCE(NIPS)	ARM(Feet)	STABILIZING MOMENT	OVERTURNING MOMENT
WEIGHT OF DAM	52.58	13.08	729.80	285.81
HEADWATER	30.35	9.42		
TAILWATER	10.11	5.79	60.59	345.75
UPLIFT	29.34	12.47		493.88
			790.49	651.55

NET HORIZONTAL FORCE= 20.25 NIPS
 NET VERTICAL FORCE= 23.24 NIPS
 NET MOMENT= 138.94KIP-Feet
 X-BAR OF FOUNDATION REACTION= 5.93 FEET
 ECCENTRICITY OF FOUNDATION REACTION FROM CENTER= 4.02 FEET
 *****FOUNDATION REACTION NOT IN CENTRAL THIRD OF BASE*****
 FOUNDATION REACTION PRESSURE= 18.85 PSIF
 OVERTURNING FACTOR OF SAFETY= 1.21
 SLIDING FACTOR OF SAFETY= .80
 DEVELOPED FRICTION FACTOR (NO SHEAR)= .87
 SLIDING WITH SHEAR FACTOR OF SAFETY= 9.34(SHEAR ACROSS FULL BASE WIDTH)
 STATIONS OF Ogee PORTION OF SECTION ARE 8.00 AND 20.20
 EQUATION OF Ogee CURVATURE IS Y= .09864X+1.05
 NUMBER OF STATIONS TO DESCRIBE DAM= 5

STATION ELEVATION
 0.00 1131.00
 8.00 1143.69
 20.20 1154.00
 22.13 1153.15
 24.20 1138.00

STOP 0